



| ESTIMATE # | DATE       | EXPIRES    |
|------------|------------|------------|
| 1199       | 08/16/2026 | 09/15/2026 |

#### CUSTOMER

Sherry Rhodes  
sherry\_rhodes@hotmail.com  
7193222284

#### SERVICE ADDRESS

2 Canal Drive  
Poquoson, VA 23662

| Structural                                                                                        | Qty     |
|---------------------------------------------------------------------------------------------------|---------|
| Concrete Piers<br><i>Concrete Piers with concrete footing 5000 psi concrete and gravel stone.</i> | 7       |
| Beam Install<br><i>Beam Made of Pressure treated (3) 2x8</i>                                      | 23      |
| Electrical Outlet<br><i>Electrical Breaker with GFI outlet.</i>                                   | 1       |
| 10% Customer discount                                                                             | -936.34 |

Subtotal \$8,427.08  
**Total \$8,427.08**

#### SCOPE OF WORK

- Install 7 concrete footings with a base of 20in wide 24in deep and 20in length and fill with 12 inches of #57 gravel stone, and 12 inches of concrete PSI 5000. Install ( ) metal power post adjustable jacks OR concrete piers to support a beam.
- Install 23 lr ft of main beam with (3)2x8 pressure treated lumber.
- Install a new GFCI-protected electrical outlet for the sump pump. Work includes providing and installing the appropriate outlet, electrical box, wiring, and connections as needed, testing the GFCI for proper operation, and verifying the sump pump operates safely from the new outlet.



| ESTIMATE # | DATE       | EXPIRES    |
|------------|------------|------------|
| 1199       | 08/16/2026 | 09/15/2026 |

## TERMS & CONDITIONS

### Notes:

- \*\*Jobsite will be left clean once completed.
- \*\*Contractor is not responsible for damage caused inside the home while repairing the foundation.
- \*\*Only 10 percent lift will be attempted when lifting and securing beams.

### Warranty:

- \*\*2 year lift.
- \*\*Stabilization guaranteed.
- \*\*12 months workmanship.

### Payment:

Deposit \$4,213.54  
Upon completion of project \$4,213.54

\*\*You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

### Cards not eligible for payment:

-Virtual Affirm credit card

## APPROVAL

This Estimate has been accepted on \_\_\_\_\_ by \_\_\_\_\_

Signature: \_\_\_\_\_